

BENCHMARK PROJECT MANAGEMENT (UK) LTD – CASE STUDY

Title

Small Retaining Wall Reconstruction

General Scope:

Take down and rebuild the length of retaining stone wall while strengthening and also improving drainage.

Work included:

- Deconstructed stone wall, clean and set aside the stone for reuse
- Build new concrete block retaining structure inclusive of weep holes
- Implementation of perforated pipe and granular drainage to rear of wall
- Excavated line trench and poured new concrete footings
- Reconstruction of set aside stone blocks to match existing style true and plum
- Adjusted existing slabs to accommodate for granular drainage

Dates:

Jan 2018

Client:

MD Group

Value:

£60,000.00

Innovation:

- The low retaining stone wall on a busy stretch of path was evidently beginning to fail and desperately needed strengthening. It was also found to be missing any type of current foundations or drainage.



Customer Satisfaction:

“What an improvement! It’s clearly built to last and we have had nothing but good comments from the nearby residents.”

MD Group Project Manager

For more information contact:
Lee Probert – Managing Director
Telephone No: 01275 545290